



Tel : +27 47 401 6400
Fax : +27 47 401 6431
Email: info@kinghintsacollege.edu.za

1. REQUEST FOR QUOTATIONS

RFQ Name: REPLACING OF INDUSTRIAL, PVC GUTTERS AND AN ADDITIONAL 5000L WATER TANKS

RFQ No: KHC/RFQ/09/2024

Specification Enquires: Mr L. Soji

Contact Details: 047 491 9847/9822

Email address: isoji@kinghintsacollege.edu.za

SCM Enquiries: Ms N. Maseme

Contact No: 047 401 6400/6437

Email address: nmaseme@kinghintsacollege.edu.za

2. SITE BRIEFING INFORMATION

SITE BRIEFING TO BE HELD AT THE FOLLOWING ADDRESS BELOW:

Venue: Teko Campus (Tracor Farms, Centane Road)

Date: 08 March 2024

Time: 10:00 am

3. SPECIFICATION

PLEASE REFER TO THE ATTACHED DOCUMENT FOR FULL SPECIFICATIONS!!!!!!!

4. MANDATORY RETURNABLE DOCUMENTS

Prospective bidders to submit the following documents:

Please submit the following compliance documents:

1. Valid SARS Tax Clearance Certificate or pin
2. Completed SBD 6.1 Preferential points claim form and submission of applicable documents outlined on Specific goals document (**Obtainable from the website**)
3. Central Supplier Database Registration proof (all report pages)
4. Completed SUPPLIER declaration forms (**Obtainable from the website**)
5. Copy of company registration certificate (CIPC Documents)
6. Certified copy of ID of director/s (**Not older than six months**)

All quotations and compliance documents MUST be emailed to the following address:
nmaseme@kinghintsacollege.edu.za

Closing Date of quotations: 15 March 2024 AT 16H00pm

PLEASE NOTE THAT NO LATE QUOTATIONS WILL BE ACCEPTED.



**REQUISITION SPECIFICATION FOR THE REPLACEMENT OF PVC GUTTERS AND ADDITION OF
5000L JOJO TANKS**

Item	Full Descriptions	Quantity
1.	Remove the existing worn-out gutters in all structures including removal of rubble on site to the nearest dumping area.	All identified structures
2.	Supply and install square White PVC Rainflow D shape gutters (100x75x0,4mm) including all the necessary accessories like downpipes, offsets, angles, bend, joiners, outlets, stop-end, brackets etc.	Admin Block only
3.	Supply and install White PVC Rainflow D shape gutters(6.000m GPE 6.01) including all the necessary accessories like downpipes, offsets, angles, bend, joiners, outlets, stop-end, brackets etc, all to be heavy duty material. SANS Approved PERMANENT STRUCTURES BLOCK A Bhishe residence BLOCK B Double Storrey residence BLOCK C Pep residence BLOCK D Soopini residence CAMPUS HALL TV-ROOM Clinic block Matrons block All classes and Computer labs Workshops	All the identified structures
4.	Supply and install 5000L JoJo tanks including construction of stands and mounting them on the stands with 3mm steel cables, cable clamps, bolts etc. PERMANENT STRUCTURES BLOCK A Bisho residence BLOCK B Double storey residence BLOCK C Pep residence BLOCK D Soopini residence CAMPUS HALL Admin block Clinic block All blocks for classes Computer labs blocks Workshop blocks	05 x 5000L Jojo tanks
5.	Hiring of scaffolding	1