



Tel : +27 47 401 6400
Fax : +27 47 401 6431
Email: Info@kinghintsacollege.edu.za

1. REQUEST FOR QUOTATION

RFQ Name: REPAIRS TO MECHANICAL ENGINEERING WORKSHOP AT TEKOS CAMPUS

RFQ No: KHC/RFQ/18/2024

Technical Enquires: Mr. M. Mpithi

Contact Details: 047 401 6400/6485

Email address: mmpithi@kinghintsacollege.edu.za

SCM Enquiries: Ms N. Maseme

Contact No: 047 401 6400/6437

Email address: nmaseme@kinghintsacollege.edu.za

2. COMPULSORY SITE BRIEFING INFORMATION

Site briefing to be held at the below address:

Venue: King Hintsa TVET College, Teko campus (Tracor farms, Centane Road)

Date: 19 July 2024

Time: 10:00 am

REQUISITION SPECIFICATION

PLEASE SEE ATTACHED DOCUMENT FOR FULL SPECIFICATIONS!!!!!!

Important Information:

Please submit the following compliance documents:

1. Valid SARS Tax Clearance Certificate or pin
2. Completed SBD 6.1 Preferential points claim form and submission of applicable documents outlined on Specific goals document (**Obtainable from the website**)
3. Central Supplier Database Registration proof (all report pages)
4. Completed SUPPLIER declaration forms (**Obtainable from the website**)
5. Copy of company registration certificate
6. Certified copy of ID of director(s) (not older than 6 months)

All quotations and compliance documents MUST be emailed to the following address:
nmaseme@kinghintsacollege.edu.za

Closing Date of quotations: 24 July 2024, 16:00 pm

PLEASE NOTE THAT NO LATE QUOTATIONS WILL BE ACCEPTED



REQUISITION SPECIFICATION

BUILDING: 26M X 20M

FLOORS: 1. Epoxy paint and remarking.

2. Joints properly cleaned & waterproofed.

GUARAGE DOORS ROLLER SHUTTERS. Three doors to be replaced.

FRONT:

DOORS: 1. Four hardwood meranti doors to be replaced

2. Burgler bars installed to all four doors.

3. Door frame must be cleaned and prepared.

BUILDING OF OFFICE, STOREROOM, CHANGING ROOMS.

OFFICE

4 x 3 = 12m²

STOREROOMS

12 x 3 m²

CHANGING ROOMS

4 x 3 = 12m²

*Roller shutter door to be removed and the section to be closed by a one brick wall.

*20m long brick wall (Internal wall), it is a one brick wall plastered on both sides and the wall is 3m high.

2 half brick walls separated, separating office and changing rooms.

Standard size hard wood meranti doors with frames installed, coated with vanish.

TEKO (OFFICE, STOREROOM, CHANGING ROOM)

CEILINGS

- 38 x 38 Timber battens for a 60m² ceiling
- 18m long cornice
- Nutec boards to cover 60m²+ cover strips.



Tel : +27 47 401 6400
Fax : +27 47 401 6431
Email: info@kinghintsacollege.edu.za

PAINT WORK (TWO COATS)

$$20 \times 3 = 60\text{m}^2 \times 2 \\ = 120\text{m}^2$$

$$26 \times 3 = 78 \times 2 \\ = 156\text{m}^2$$

276m² outside

276m² inside

=552m²

INTERNAL WALLS (TWO COATS)

Office, storeroom, changing room.

$$20 \times 3 = 60\text{m}^2$$

$$3 \times 3 = 9\text{m}^2 \times 3$$

$$= 27\text{m}^2$$

PAINT TO THE CEILINGS

Two coats on 60m² ceiling.

PAINT TO THE ROOF

Roof area = 1040 m²

Replace clear sheets (1.5 m high) to suit the length of 66 metres.